

PART 5
SCHEDULE OF RATES

SCHEDULE OF RATES

1 This Part 5 – Schedule of Rates shall be read in conjunction with the other documents, which together shall form the Contract Document.

2 This Schedule of Rates herein shall be filled by the Tenderer and submitted together with its Tender. All rates shall be full inclusive rates enforceable for the entire duration of the Contract including all extensions thereto and shall not be subjected to any amendment.

3 All prices quoted shall include all incidental and contingent costs and expenses such as supply of qualified labour, all necessary equipment and materials, transport, etc. to install the replacement parts and equipment (or its equivalent) listed in this Schedule (except Item 20) for the proper functioning of the system after replacement. No price adjustment shall be made for any error. The School will not consider any claims from the Contractor arising from any increase in expenses such as for labour, materials, equipment, tools, transport, exchange rates, taxation, etc. throughout the duration of the Contract.

4 The Contractor shall cater for all reasonable risks in its tender percentage adjustment to this Schedule of Rates in Part 4 – Form of Tender.

Item	Description	Unit of Measure	Unit Rate (S\$)
1	IP CCTV Camera 2MP Varifocal Dome Network Camera Varifocal motorized lens 2.7 – 13.5 mm Max resolution – 1920 x 1080 Image sensor – 1/2.7” 2MP	Number	210
2	PTZ CCTV Camera 4 MP 25X IR Network Speed Dome PTZ CCTV camera	Number	660
3	Network Video Recorder Up to 16 IP camera inputs. 16-ch synchronous playback. Minimum 30 days of recording and playback.	Number	2500
4	10 TB HDD Standard Fast Format (512e / 4 Kn) POH per year 24 x 7 – 8760	Number	490

PART 5 SCHEDULE OF RATES

5	POE Switch (for additional cameras) 8 ports fast ethernet unmanaged	Number	90
6	POE Switch (for existing standalone cameras) 16 ports fast ethernet unmanaged	Number	280
7	CMS - Workstation Central - Workstation	Number	2660
8	CMS - Network Video Recorder Up to 128-ch IP camera inputs. Minimum 30 days of recording and playback	Number	3690
9	CMS - LED Monitor 24 inch with E-LED backlight	Number	220
10	Cabling and installation Cat UTP (Unshielded Twisted Pair) cabling	Lot	650
11	Cabling and installation Indoor OM3 (Optimized Multimode) Fiber Optics cabling	Lot	950
12	Standalone CCTV with SD card 256 GB	Number	300
13	6 Zones Hybrid Control Panel Expandable to 16 Zones, w/Cabinet, English Manuals & Cam-Lock & 2 keys	Number	350
14	7AH Backup Battery	Number	120
15	DSC PowerSeries ICON LCD Keypad or equivalent	Number	120
16	Surface Magnetic Contact	Pair	8
17	Dual Technology Motion Detector	Number	80
18	Indoor Siren c/w Blue Strobelight, Tampered	Number	40
19	Provision of labour including of material, transport for standby and/or additional request	Lot	300

PART 5 SCHEDULE OF RATES

<i>Any other individual items to be included: (Please use separate sheets if insufficient)</i>			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			

Name of Tenderer
Official Company Stamp

Name of Authorised Personnel
Designation, Signature and Date